
# Exhibit 1C Substation Plans





BOWERS WIND PROJECT
PENOBSCOT COUNTY, MAINE
CHAMPLAIN WIND, LLC
DDLE STREET, 3RD FLOOR, PORTLAND, N **ONE LINE DIAGRAM** 


firstwind clean energy, MADE HERE


SHEET


<u>DWG.</u> R PERMIT 106-01-1000
































### **GENERAL EROSION CONTROL NOTES:**

- ALL EROSION & SEDIMENT CONTROL MEASURES SHALL BE INSTALLED & MAINTAINED IN ACCORDANCE WITH THE MAINE EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES BY THE CUMBERLAND COUNTY SOIL AND WATER CONSERVATION DISTRICT AND THE MAINE DEPARTMENT OF ENVIRONMENTAL PROTECTION DATED MARCH. 2003 (AS REVISED).
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONDUCTING STORM WATER MANAGEMENT PRACTICES IN ACCORDANCE WITH LOCAL REGULATIONS AND GOVERNING AUTHORITIES AND SHALL BE RESPONSIBLE FOR ANY FINES RESULTING FROM EROSION CONTROL VIOLATIONS.
- EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE START OF CONSTRUCTION AND SHALL BE MAINTAINED UNTIL FINAL STABILIZATION IS ACHIEVED.
- 4. THE CONTRACTOR SHALL PROVIDE PROPER EROSION CONTROL AND DRAINAGE MEASURES IN ALL AREAS OF WORK. PRIOR TO BEGINNING EXCAVATION WORK, SILT FENCE SHALL BE INSTALLED. EROSION CONTROL MEASURES SHOWN ON THE DRAWINGS ARE A MINIMUM, CONTRACTOR SHALL TAKE ALL OTHER NECESSARY MEASURES TO CONTROL EROSION. EROSION CONTROL MEASURES SHALL ALSO BE INSTALLED AT THE DOWNGRADIENT PERIMETER OF THE TOPSOIL STOCKPILES. ALL DISTURBED EARTH SURFACES SHALL BE STABILIZED IN THE SHORTEST PRACTICAL TIME AND TEMPORARY EROSION CONTROL DEVICES SHALL BE EMPLOYED UNTIL SUCH TIME AS ADEQUATE SOIL STABILIZATION HAS BEEN ACHIEVED. TEMPORARY STORAGE OF EXCAVATED MATERIAL SHALL BE STABILIZED IN A MANNER THAT WILL MINIMIZE EROSION.
- 5. THE ON-SITE PLAN COORDINATOR SHALL INSPECT ESC MEASURES ONCE EVERY SEVEN DAYS AND WITHIN 24 HOURS OF SIGNIFICANT RUNOFF EVENTS, INCLUDING THOSE THAT RESULT IN DISCHARGE OF STORMWATER FROM THE SITE. DAILY INSPECTIONS OF ESC MEASURES SHALL BE CONDUCTED DURING THE WINTER CONSTRUCTION PERIOD (NOVEMBER 1 -APRIL 15). REPAIRS SHALL BE MADE AS NECESSARY. ACCUMULATED SEDIMENT TRAPPED BY ESC DEVICES SHALL BE REMOVED AS
- TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES SHALL BE REMOVED AND THOSE ADJACENT AREAS RESTORED UPON COMPLETION OF THE WORK OR WHEN SO ORDERED BY THE ON-SITE PLAN COORDINATOR. EXPOSED SOIL RESULTING FROM REMOVAL OF TEMPORARY ESC MEASURES SHALL BE RAKED, SEEDED, AND MULCHED OR MATTED AS NEEDED.
- 7. PERMANENT SEED MIX SHALL BE USED AS EARLY AS PRACTICABLE BETWEEN 05/15 AND 9/1.
- 8. TEMPORARY SEED MIX SHALL BE USED BETWEEN 9/1 AND 5/14 AND SHALL MEET THE FOLLOWING

SEED	% WEIGHT	% GERMINATIC
WINTER RYE RED FESCUE (CREEPING) PERENNIAL RYE GRASS RFD CLOVER		85 MIN 80 MIN 90 MIN 90 MIN
OTHER CROP GRASS NOXIOUS WEED SEED INERT MATTER	0.5 MAX 0.5 MAX 1.0 MAX	

- 9. TEMPORARY MULCHING IS TO BE APPLIED TO ALL DISTURBED AREAS WITHIN 21 DAYS OF INITIAL DISTURBANCE AND TO AREAS LEFT INACTIVE AND UNSTABILIZED FOR A PERIOD GREATER THAN 7 DAYS AT A RATE OF 2 TONS/ACRE UNLESS:
  - i) STABILIZATION IS NOT REQUIRED IF WORK IS TO CONTINUE IN THE AREA WITHIN THE NEXT 24 HOURS AND THERE IS NO PRECIPITATION FORECAST FOR THE NEXT 24 HOURS,
  - ii) STABILIZATION IS NOT REQUIRED IF THE WORK IS OCCURRING IN A SELF-CONTAINED EXCAVATION (i.e. NO OUTLET) WITH A DEPTH OF 2 FEET OR GREATER (e.g. UTILITY
- 10. PERMANENT SEED MIX SHALL BE USED AS EARLY AS PRACTICABLE BETWEEN 05/15 AND 9/1 AND MEET THE FOLLOWING CRITERIA: RED FESCUE SHEEP FESCUE 25% RFD TOP
- ANNUAL RYE 10% 11. WETLAND SEED MIX SHALL MEET THE FOLLOWING CRITERIA:

10%

NODDING BUR MARIGOLD	5%
FOX SEDGE	13%
CREEPING BENTGRASS	14%
RIVERBANK WILD RYE	8%
VIRGINIA WILD RYE	14%
SOFT RUSH	2%
SENSITIVE FEM	1.5%
BLUE VERVAIN	1%
BLACKWELL SWITCH GRASS	25%
GREY DOGWOOD	0.5%
CREEPING RED FESCUE	18%

WHITE CLOVER


- 12. THE METHOD OF STRIPPING VEGETATION SHALL BE SUCH AS TO MINIMIZE EROSION. FILLS SHALL BE PLACED AND COMPACTED IN SUCH A MANNER THAT SOIL SLIDING AND EROSION IS MINIMIZED GRADING SHALL BE DONE IN SUCH A MANNER AS NOT TO DIVERT WATER ON TO ADJOINING
- 13. EROSION CONTROL BLANKET OR EQUIVALENT SHALL BE USED TO STABILIZE ALL DITCHES AND SIDESLOPES STEEPER THAN 3H: 1V.
- 14. SEDIMENT LOGS AND OR EROSION CONTROL MIX BERMS MAY BE SUBSTITUTED FOR SILT FENCE BY THE ON-SITE PLAN COORDINATOR AS CONDITIONS DICTATE.
- 15. PLACE EXCAVATED MATERIAL ON THE UP GRADIENT SIDE OF THE EXCAVATION TO THE EXTENT POSSIBLE, EXCESS SOILS ARE TO BE TRANSPORTED TO AN OFF-SITE UPLAND LOCATION FOR STOCKPILING. WETLAND SOILS SHALL BE STOCKPILED SEPARATELY FROM UPLAND SOILS.

## WINTER CONSTRUCTION NOTES:

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLETING ALL WINTER EROSION AND SEDIMENT CONTROL IN ACCORDANCE WITH SECTION A-3 OF "MAINE EROSION AND SEDIMENTATION CONTROL
- WINTER EXCAVATION AND EARTHWORK SHALL BE COMPLETED SUCH THAT FOR ANY GIVEN SEGMENT OF THE PROJECT AREA, NO MORE AREA THAN CAN BE STABILIZED IN A ONE-WEEK PERIOD IS TO BE EXPOSED AT ANY GIVEN TIME. MULTIPLE SEGMENTS AT DIFFERENT LOCATIONS WITHIN THE PROJECT AREA CAN BE EXPOSED CONCURRENTLY.
- DISTURBED AREAS ARE TO BE LIMITED TO AREAS WHERE WORK IS TO BE COMPLETED WITHIN 15 DAYS AND CAN BE MULCHED IN ONE DAY PRIOR TO A SNOW EVENT.
- AREAS OF DISTURBED SOIL SHALL BE STABILIZED AT THE END OF EACH WORK DAY, WITH THE FOLLOWING EXCEPTIONS: (1) IF NO RUNOFF EVENT IS FORECAST FOR WITHIN 24 HOURS AND WORK WILL RESUME IN THE SAME DISTURBED AREA WITHIN 24 HOURS AND/OR (2) DISTURBED AREAS THAT COLLECT AND RETAIN RUNOFF, SUCH AS OPEN UTILITY TRENCHES OR FOUNDATIONS, WHICH REQUIRE STABILIZATION AT THE END OF EACH WORK WEEK.
- SNOW PILING SHALL OCCUR WITHIN THE DESIGNATED LIMITS OF DISTURBANCE.
- DRAINAGE STRUCTURES SHALL BE KEPT OPEN AND FREE OF SNOW AND ICE DAMS.
- SILT FENCE AND OTHER PRACTICES REQUIRING EARTH DISTURBANCE SHALL BE INSTALLED PRIOR TO FROZEN GROUND CONDITIONS. SILT FENCE MAY BE INSTALLED WITH STONE BACKING DURING FROZEN GROUND CONDITIONS.
- MULCH USED FOR TEMPORARY STABILIZATION SHALL BE APPLIED AT 4 TONS/ACRE WITH AN 80 TO 90 PERCENT UNIFORM COVER AND TRACKED IN TO PREVENT REMOVAL BY WIND.
- 9. PRIOR TO STABILIZATION, SNOW AND/OR ICE SHALL BE REMOVED TO LESS THAN 1 INCH THICKNESS.
- 10. STONE SHALL CONSTRUCTION ENTRANCES BE USED TO STABILIZE AREAS WHERE CONSTRUCTION VEHICLE TRAFFIC IS ANTICIPATED. STONE ENTRANCES SHALL BE AT LEAST 14 FEET WIDE TO ACCOMMODATE VEHICULAR TRAFFIC.
- 11. ALL SLOPES LESS THAN 3H:1V SHALL BE MULCHED AT 4 TONS/ACRE AND TRACKED IN.
- 12. THE SITE STABILIZATION SCHEDULE BEFORE WINTER SHALL BE AS FOLLOWS:

SEPTEMBER 15 ALL DISTURBED AREAS MUST BE SEEDED AND MULCHED. ALL SLOPES MUST BE STABILIZED, SEEDED AND MULCHED. ALL GRASS LINED DITCHES AND CHANNELS MUST BE STABILIZED WITH MULCH OR AN EROSION CONTROL BLANKET. OCTOBER 1 ALL DISTURBED AREAS TO BE PROTECTED WITH AN ANNUAL GRASS MUST BE SEEDED AT A SEEDING RATE OF 3 POUNDS PER 1000 SQ-FT AND MULCHED. NOVEMBER 15 ALL STONE-LINED DITCHES AND CHANNELS MUST BE CONSTRUCTED. SLOPES THAT ARE COVERED WITH RIPRAP MUST BE CONSTRUCTED BY THAT DATE ALL DISTURBED AREAS WHERE THE GROWTH OF VEGETATION FAILS TO BE AT DECEMBER 1 LEAST THREE INCHES TALL OR AT LEAST 75% OF THE DISTURBED SOIL IS COVERED


BY VEGETATION, MUST BE PROTECTED FOR OVER-WINTER.




# 1. LAY HAYBALES FLAT ON EXISTING GROUND AND MINIMIZE GAPS BETWEEN

- 2. PLACE HAYBALES PARALLEL TO EXISTING GRADE CONTOURS TO PREVENT CONCENTRATED FLOW. DO NOT USE HAYBALE FENCE IN AREAS OF CONCENTRATED FLOW.
- 3. DRIVE WOODEN STAKES INTO EXISTING GROUND A MINIMUM OF 12 INCHES.
- 4. WITHIN 21 DAYS HAYBALES SHALL BE REMOVED/REPLACED IF DAMAGED, ROTTED, OR OTHERWISE NON-FUNCTIONAL.
- 5. HAYBALES ARE TO BE SPREAD AS MULCH AT THE COMPLETION OF CONSTRUCTION ACTIVITIES, DO NOT RE-USE HAYBALES.


### HAYBALF FENCE DETAIL NOT TO SCALE







- 1. EROSION CONTROL MIX SHALL CONTAIN A WELL-GRADED MIXTURE OF PARTICLE SIZE AND MAY CONTAIN ROCKS LESS THAN 4-INCHES IN DIAMETER. EROSION CONTROL MIX MUST BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH. THE MIX COMPOSITION SHALL MEET THE FOLLOWING
- THE ORGANIC MATTER CONTENT SHALL BE BETWEEN 80 AND 100 PERCENT,
- DRY WEIGHT BASIS. PARTICLE SIZE BY WEIGHT SHALL BE 100 PERCENT PASSING A 6-INCH SCREEN AND A MINIMUM OF 70 PERCENT, MAXIMUM OF 85 PERCENT, PASSING A 3/4-INCH SCREEN
- THE ORGANIC PORTION NEEDS TO BE FIBROUS AND ELONGATED. LARGE PORTIONS OF SILTS, CLAYS OR FINE SANDS ARE NOT ACCEPTABLE IN
- 5. SUITABLE SALTS CONTENT SHALL BE LESS THAN 4.0 MINIMUM.
  THE BARRIER MUST BE PLACED ALONG A RELATIVELY LEVEL CONTOUR. TALL GRASSES MAY NEED TO BE CUT TO AVOID VOID SPACES THAT WOULD ALLOW FINES
- TO WASH UNDER THE BARRIER FROZEN GROUND, OUTCROPS OF BEDROCK AND VERY ROOTED FORESTED AREAS ARE LOCATIONS WHERE BERMS OF EROSION CONTROL MIX ARE MOST PRACTICAL

## <u>EROSION CONTROL MIX BERM DETAIL</u>




RIPRAP SLOPE STABILIZATION DETAIL NOT TO SCALE






- 1. REINFORCED FENCE CAN BE USED IN PLACE OF TWO LAYERS OF CONVENTIONAL SILT FENCE WHEN WORKING IN ENVIRONMENTALLY SENSITIVE AREAS SUCH AS WITHIN 250' OF A LAKE, POND, RIVER, STREAM, OR BROOK, WITHIN 100 FEET A WETLAND OR STREAM CROSSING OR OTHER SENSITIVE AREAS.
- 2. WIRE REINFORCING NOT NECESSARY FOR NON-SENSITIVE INSTALLATIONS. FOR CONVENTIONAL SILT FENCE, INSTALL PER DETAIL MINUS WOVEN WIRE FENCE.
- 3. SILT FENCE SHALL BE PLACED ON SLOPE CONTOURS TO MAXIMIZE PONDING EFFICIENCY.
- 4. INSPECT AND REPAIR FENCE AFTER EACH STORM EVENT AND REMOVE SEDIMENT WHEN NECESSARY.
- 5. DO NOT PLACE SILT FENCE IN STREAMS OR CONCENTRATED FLOW CONDITIONS.
- 6. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES.
- 7. FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION. FENCE SHALL BE WOVEN WIRE, 6" MAXIMUM MESH OPENING.
- 8. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVERLAPPED BY SIX INCHES AND FOLDED. FILTER CLOTH SHALL BE EITHER FILTER X, MIRAFI 100X, STABILINKA T140N, OR APPROVED EQUIVALENT.
- 9. PREFABRICATED UNITS SHALL BE GEOFAB, ENVIROFENCE, OR APPROVED EQUIVALENT.
- 10. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN SEDIMENT REACHES HALF OF FABRIC HEIGHT.
- 11. REMOVED SEDIMENT SHALL BE DEPOSITED TO AN UPLAND AREA THAT WILL NOT CONTRIBUTE SEDIMENT OFF-SITE AND CAN BE PERMANENTLY STABILIZED.

### SILT FENCE DETAII NOT TO SCALE






# NOT TO SCALE


- 1. EROSION CONTROL MIX SHALL CONTAIN A WELL-GRADED MIXTURE OF PARTICLE SIZE AND MAY CONTAIN ROCKS LESS THAN 4-INCHES IN DIAMETER. EROSION CONTROL MIX MUST BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH. THE MIX COMPOSITION SHALL MEET THE
- FOLLOWING STANDARDS. THE ORGANIC MATTER CONTENT SHALL BE BETWEEN 80 AND 100 PERCENT, DRY WEIGHT BASIS. PARTICLE SIZE BY WEIGHT SHALL BE 100 PERCENT PASSING A 6-INCH SCREEN AND A MINIMUM OF 70 PERCENT, MAXIMUM OF 85 PERCENT, PASSING A 3/4-INCH SCREEN
- THE ORGANIC PORTION NEEDS TO BE FIBROUS AND ELONGATED. LARGE PORTIONS OF SILTS, CLAYS OR FINE SANDS ARE NOT ACCEPTABLE IN THE MIX.
- SUITABLE SALTS CONTENT SHALL BE LESS THAN 4.0 MINIMUM. 2. THE BARRIER MUST BE PLACED ALONG A RELATIVELY LEVEL CONTOUR. TALL GRASSES MAY NEED TO BE
- CUT TO AVOID SPACES THAT WOULD ALLOW FINES TO WASH UNDER THE BARRIER 3. FROZEN GROUND, OUTCROPS OF BEDROCK AND VERY ROOTED FORESTED AREAS ARE LOCATIONS WHERE BERMS OF EROSION CONTROL MIX ARE MOST PRACTICAL AND EFFECTIVE.

NOT TO SCALE




- 1. CRUSHED GRAVEL SHALL BE MDOT 703.10
- 2. SUBBASE FILL MATERIAL SHALL BE MDOT 703.06, TYPE C, PLACED AND COMPACTED IN 6-INCH LIFTS.
- 3. SUBGRADE MATERIAL SHALL BE FREE OF ORGANICS, ROCKS, DEBRIS AND OTHER DELETERIOUS MATERIALS AND SHALL NOT BE WET OR FROZEN DURING PLACEMENT OF SUBBASE MATERIAL.

GRAVEL DRIVE DETAIL NOT TO SCALE




- 1. CRUSHED STONE SHALL BE MDOT 703.12.
- 2. SUBBASE FILL MATERIAL SHALL BE MDOT 703.06, TYPE C, PLACED AND COMPACTED IN 6-INCH LIFTS.
- 3. SUBGRADE MATERIAL SHALL BE FREE OF ORGANICS, ROCKS, DEBRIS AND OTHER DELETERIOUS MATERIALS AND SHALL NOT BE WET OR FROZEN DURING PLACEMENT OF SUBBASE MATERIAL.

YARD CRUSHED STONE SURFACING AND GRAVEL SUBBASE DETAIL NOT TO SCALE



NOTE: EROSION CONTROL FABRIC (SC150 BY NORTH AMERICAN GREEN, OR EQUAL) SHALL BE INSTALLED ON ALL SLOPES OF 3H: 1V OR STEEPER.

> <u>LOAM AND SEED DETAIL</u> NOT TO SCALE



- 1. ALL TREES, BRUSH, STUMPS, OBSTRUCTIONS, AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED AND DISPOSED OF SO AS NOT TO INTERFERE WITH THE PROPER FUNCTIONING OF THE WATERWAY.
- 2. THE WATERWAY SHALL BE EXCAVATED OR SHAPED TO LINE, GRADE, AND CROSS SECTION AS REQUIRED TO MEET THE CRITERIA SPECIFIED HEREIN, AND BE FREE OF BANK PROJECTIONS OR OTHER IRREGULARITIES WHICH
- 3. FILLS SHALL BE COMPACTED AS NEEDED TO PREVENT UNEQUAL SETTLEMENT THAT WOULD CAUSE DAMAGE IN
- 4. ALL EARTH REMOVED AND NOT NEEDED IN CONSTRUCTION SHALL BE SPREAD OR DISPOSED OF SO THAT IT WILL NOT INTERFERE WITH THE FUNCTIONING OF THE WATERWAY.
- 5. GRASSED WATERWAY SHALL BE FINISHED AND STABILIZED AS FOLLOWS:
- A. A MINIMUM OF 4" SCREENED LOAM SHALL BE PROVIDED AS TOPSOIL.
- B. DURING THE WINTER MONTHS, THE PERIMETER SWALE IS TO BE LINED WITH EITHER MULCH OR EROSION CONTROL BLANKET AS GROUND CONDITIONS DICTATE.
- C. THE PERIMETER SWALE IS TO BE MULCHED AND SEEDED TO ENCOURAGE A GOOD CATCH OF GRASS AT THE COMPLETION OF CONSTRUCTION WHEN WINTER CONDITIONS HAVE SUBSIDED. SEED MIX SHALL MATCH ONE OF THE FOLLOWING:

BIRDSFOOT TREFOIL OR LADINO CLOVER TALL FESCUE OR SMOOTH BROMEGRASS REDTOP KENTUCKY BLUEGRASS CREEPING RED FESCUE 36% PERENNIAL RYEGRASS 19%


> GRASSED SWALE DETAIL NOT TO SCALE

> > ISSUED FOR PERMIT

 $\circ$ OJE  $Z \cap$ PR WIND

SE AIL BOWERS PENOBSCO 

SHEET



- 1. BURY THE TOP END OF THE MESH MATERIAL IN A 12" TRENCH. BACKFILL AND TAMP TRENCH, SECURE END WITH STAPLES AT 6" SPACING, 4" DOWN
- 2. FLOW DIRECTION JOINTS TO HAVE UPPER END OF LOWER STRIP BURIED WITH UPPER LAYERS OVERLAPPED 4" AND STAPLED. OVERLAP B OVER A.
- 3. LATERAL JOINTS TO HAVE 4" OVERLAP OF STRIPS. STAPLE 18" ON CENTER.

NOTES:

1. CONCRETE: 5,000 PSI MINIMUM STRENGTH AT 28

2. STEEL REINFORCING - ASTM A-615, GRADE 60.

4. DESIGNED TO MEET ASTM C858 AND ACI 318 WITH

6. PIPE SLEEVES SHALL BE FLEXIBLE LOCK-JOINT OR

8. TANK SHALL BE OLDCASTLE PRECAST CST-8,000. 8,000 GALLON COMMERCIAL SEPTIC TANK OR

9. DIMENSIONS OF TANK MAY VARY DEPENDING ON THE OIL STORAGE VOLUME OF THE TRANSFORMER.

SECTION B-B

7. TANK JOINTS SHALL BE KENT SEAL 2" BUTYL

3. COVER TO STEEL - 1" MIN.


AASHTO HS-20 LOADING.

EQUAL.

5. EARTH COVER - 0 TO 5 FEET MAX.

- 4. STAPLE OUTSIDE LATERAL EDGE 2' ON CENTER.
- 5. WIRE STAPLES TO BE MIN. OF # 11 WIRE 6" LONG AND 1-1/2" WIDE.
- 6. USE NORTH AMERICAN GREEN DS 150 OR APPROVED EQUAL.

EROSION CONTROL BLANKET DETAIL (DITCH) NOT TO SCALE





# BILCO ALUMINUM ACCESS - HATCH (SET 6" ABOVE FINISHED $INLET\ INV = TBD$

GRADE) OUTLET INV = TBD 7'-9"

SECTION A-A


OIL/WATER SEPARATOR DETAIL NOT TO SCALE






- 1. STONE WILL BE PLACED ON A FILTER FABRIC FOUNDATION TO THE LINES, GRADES AND LOCATIONS SHOWN IN THE PLAN.
- 2. SET SPACING OF CHECK DAMS TO ASSUME THAT THE ELEVATIONS OF THE CREST OF THE DOWNSTREAM DAM IS AT THE SAME ELEVATION OF THE TOE OF THE DOWNSTREAM DAM.
- 3. EXTEND THE STONE A MINIMUM OF 1.5 FEET BEYOND THE DITCH BANKS TO PREVENT CUTTING AROUND THE DAM.
- 4. PROTECT THE CHANNEL DOWNSTREAM OF THE LOWEST CHECK DAM FROM SCOUR AND EROSION WITH STONE OR LINER AS
- 5. ENSURE THAT CHANNEL APPURTENANCES SUCH AS CULVERT ENTRANCES BELOW CHECK DAMS ARE NOT SUBJECT TO DAMAGE OR BLOCKAGE FROM DISPLACED STONE.

### STONE CHECK DAM DETAIL NOT TO SCALE




- 1. USE 2" TO 3" STONE.
- 2. PLACE STONE OVER GEOTEXTILE.
- 3. ONCE THE AREAS UPGRADIENT FROM THE CHECK DAM ARE STABILIZED BY VEGETATION, THE SEDIMENT
- TRAPPED BEHIND/WITHIN THE DAM SHALL BE RELOCATED TO AN AREA UNDERGOING FINAL GRADING OR
- 4. ONCE UPGRADIENT AREAS ARE STABILIZED, DAMS SHALL BE FLATTENED AND GRADED IN A MANNER WHICH PROTECTS THE AREA FROM EROSION AND CHANNEL BLOCKAGE.
- 5. GEOTEXTILE MUST BE REMOVED AND DISPOSED OF OFFSITE.
- 6. THE AREA CONTRIBUTING TO THE CHECK DAM SHALL NOT EXCEED 10 ACRES.


TEMPORARY CULVERT INLET PROTECTION DETAIL NOT TO SCALE



# TYPICAL PIPE TRENCH DETAIL



NOT TO SCALE



1) THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE TOP DRESSING. REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.

- 2) WHEN NECESSARY, WHEELS SHALL BE CLEANED PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF WAY.
- 3) WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.
- 4) ALL SEDIMENT SPILLED, DROPPED, OR WASHED ONTO PUBLIC RIGHT-OF-WAY MUST BE REMOVED IMMEDIATELY.
- 5) PLACE STONE ON GEOTEXTILE FABRIC.

TEMPORARY CONSTRUCTION ENTRANCE DETAIL

PROJEC

WIND

BOWERS

AND.

SHEET ISSUED FOR PERMIT

