



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE  
04333-0016

JOHN ELIAS BALDACCI  
GOVERNOR

DAVID A. COLE  
COMMISSIONER

March 11, 2008  
Subject: Gardiner & West Gardiner  
Project No. IM- 1592(900) E  
Pin No. 015929.00  
**Amendment No. 1**

Dear Sir/Ms:

Please make the following changes to the Bid Documents:

In the bid book, **REMOVE** the SCHEDULE OF ITEMS dated 08022 , five pages total (pages 3 thru 7) and **REPLACE** with the attached new SCHEDULE OF ITEMS, dated 080311, five pages total.

In the Bid Book, **ADD** the attached SPECIAL PROVISION, SECTION 639, ENGINEERING FACILITIES, (Telephone), dated March 11, 2008, one page total.

The following question has been received:

**Question:** In the typical sections for exit 49 the description of work is the travel lane only, however the Construction Notes are showing the stations for exit 49, remarks are to mill and fill full width for a portion of the ramp and travel lane only for the rest of the ramp. What is the width that the ramp will be milled and filled at?

**Response:** The construction notes are correct.

Consider these changes and information prior to submitting your bid on **March 19, 2008**.

Sincerely,

Scott Bickford  
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015929.00

PROJECT(S): IM-1592(900)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.202 REMOVING PAVEMENT SURFACE	45000.000 SY				
0020	203.242 DIRTY BORROW	150.000 CY				
0030	205.51 WIDENING OF EXISTING SHOULDER - PLAN QUANTITY	800.000 SY				
0040	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	3500.000 T				
0050	403.210 HOT MIX ASPHALT 9.5 MM HMA	1200.000 T				
0060	403.211 HOT MIX ASPHALT (SHIMMING)	100.000 T				
0070	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	100.000 T				
0080	409.15 BITUMINOUS TACK COAT - APPLIED	2300.000 G				
0090	424.3331 ASPHALT LOW MODULUS CRACK SEALER, APPLIED	1750.000 LB				
0100	424.3333 LOW MODULUS JOINT SEALER, APPLIED	11300.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015929.00

PROJECT(S): IM-1592(900)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	606.1721 BRIDGE TRANSITION - TYPE 1	2.000 EA				
0120	606.1722 BRIDGE TRANSITION - TYPE 2	2.000 EA				
0130	606.178 GUARDRAIL BEAM	125.000 LF				
0140	606.24 GUARDRAIL TYPE 3D - SINGLE RAIL	187.500 LF				
0150	606.35 GUARDRAIL DELINEATOR POST	2.000 EA				
0160	606.352 REFLECTORIZED BEAM GUARDRAIL DELINEATORS	125.000 EA				
0170	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	26.000 EA				
0180	606.362 GUARDRAIL ADJUSTED	1000.000 LF				
0190	606.367 REPLACE UNUSABLE EXISTING GUARDRAIL POSTS	5.000 EA				
0200	606.79 GUARDRAIL 350 FLARED TERMINAL	8.000 EA				
0210	606.792 GUARDRAIL 350 MEDIAN TERMINAL SYSTEM	2.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015929.00

PROJECT(S): IM-1592(900)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	2.000 EA				
0230	612.06 BITUMINOUS SEALING - BLACK	150.000 SY				
0240	613.319 EROSION CONTROL BLANKET	1500.000 SY				
0250	618.14 SEEDING METHOD NUMBER 2	25.000 UN				
0260	619.12 MULCH	25.000 UN				
0270	627.618 12 INCH SOLID WHITE PAVEMENT MARK LINE	4000.000 LF				
0280	627.72 6 INCH WHITE PAVEMENT MARKING LINE	30000.000 LF				
0290	627.74 6 INCH YELLOW PAVEMENT MARKING LINE	15000.000 LF				
0300	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	50.000 SF				
0310	627.781 TEMPORARY 6 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	45000.000 LF				
0320	629.05 HAND LABOR, STRAIGHT TIME	25.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015929.00

PROJECT(S): IM-1592(900)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	50.000 HR				
0340	631.133 SKID STEER (INCLUDING OPERATOR)	25.000 HR				
0350	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	100.000 HR				
0360	639.18 FIELD OFFICE TYPE A	1.000 EA				
0370	645.306 FLEXIBLE REFLECTORIZED DELINEATOR	25.000 EA				
0380	652.30 FLASHING ARROW BOARD	1.000 EA				
0390	652.33 DRUM	150.000 EA				
0400	652.34 CONE	150.000 EA				
0410	652.35 CONSTRUCTION SIGNS	500.000 SF				
0420	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	44.000 CD				
0430	652.38 FLAGGER	100.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015929.00

PROJECT(S): IM-1592(900)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	652.41 PORTABLE - CHANGEABLE MESSAGE SIGN	1.000 EA				
0450	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0460	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

**SPECIAL PROVISION**  
**SECTION 639**  
**ENGINEERING FACILITIES**  
**(Telephone)**

639.03 General

Paragraph 1 is amended as follows:

The filed office shall be required to remain in place November 26, 2008.

639.09 Telephone

Paragraph 1 is amended as follows:

The contractor shall provide **two** telephone lines and two telephones,....

Add-

In addition the contractor will supply one computer broadband connection and modem lease. The type of connection supplied will be contingent upon the availability of services (i.e. DSL or Cable Broadband). It shall be the contractor's option to provide dynamic or static IP addresses through the service. **The selected service will have a minimum downstream connection of 1.5 Mbps and 384 Kbps upstream.** The contractor shall be responsible for the installation charges and all reinstallation charges following suspended periods. Monthly service and maintenance charges shall be billed by the Internet Service Provider (ISP) directly to the contractor.