

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015090.00

PROJECTS

015090.00

COUNTY : PENOBSCOT

CONTRACT ID : 015090.00

SCOPE OF WORK: RED BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK. IN PENOBSOT COUNTY, PROJECT IS LOCATED ON US ROUTE 2 OVER PENJEJAWOCK STREAM APPROXIMATELY 0.5 MILES WEST OF THE TOWN LINE.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	05/24/10	\$ 750.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015090.00

PROJECT(S): 015090.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 Construction Items						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	1400.000 CY				
0030	203.24 COMMON BORROW	1200.000 CY				
0040	203.25 GRANULAR BORROW	1100.000 CY				
0050	203.4539 LEVELING SAND	15.000 CY				
0060	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	50.000 CY				
0070	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	230.000 CY				
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1258.000 CY				
0090	403.207 HOT MIX ASPHALT 19.0 MM HMA	270.000 T				
0100	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	300.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015090.00

PROJECT(S): 015090.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	409.15 BITUMINOUS TACK COAT - APPLIED	25.000 G				
0120	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0130	502.56 CONCRETE FILL	100.000 CY				
0140	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	30000.000 LB				
0150	503.13 REINFORCING STEEL, PLACING	30000.000 LB				
0160	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			
0170	510.10 SPECIAL DETOUR ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED	LUMP	LUMP			
0180	511.07 COFFERDAM:	LUMP	LUMP			
0190	511.07 COFFERDAM:	LUMP	LUMP			
0200	512.081 FRENCH DRAINS	LUMP	LUMP			
0210	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015090.00

PROJECT(S): 015090.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	30.000 SY				
0230	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0240	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			
0250	605.095 6 INCH UNDERDRAIN TYPE B - PIPE ONLY	164.000 LF				
0260	605.10 6 INCH UNDERDRAIN OUTLET	40.000 LF				
0270	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	410.000 LF				
0280	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	6.000 EA				
0290	606.79 GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0300	609.31 CURB TYPE 3	180.000 LF				
0310	610.08 PLAIN RIPRAP	500.000 CY				
0320	610.16 HEAVY RIPRAP	300.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015090.00

PROJECT(S): 015090.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	613.319 EROSION CONTROL BLANKET	300.000 SY				
0340	615.07 LOAM	30.000 CY				
0350	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	5.000 UN				
0360	619.1201 MULCH - PLAN QUANTITY	5.000 UN				
0370	619.1401 EROSION CONTROL MIX	50.000 CY				
0380	620.6012 HDPE GEOMEMBRANE	130.000 SY				
0390	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	900.000 LF				
0400	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0410	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				
0420	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0430	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	20.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015090.00

PROJECT(S): 015090.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0450	635.14 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	1050.000 SF				
0460	639.19 FIELD OFFICE TYPE B	1.000 EA				
0470	652.31 TYPE I BARRICADE	10.000 EA				
0480	652.312 TYPE III BARRICADE	10.000 EA				
0490	652.33 DRUM	20.000 EA				
0500	652.34 CONE	40.000 EA				
0510	652.35 CONSTRUCTION SIGNS	320.000 SF				
0520	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0530	652.38 FLAGGER	40.000 HR				
0540	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015090.00

PROJECT(S): 015090.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

