



SCALE IN FEET BAR LENGTHS MEASURE 1-INCH ON 22 IN. X 34IN. **PRINT** 

EXISTING 1 FT CONTOUR PROPOSED 1 FT CONTOUR BUILDING **EXISTING RIVER ALIGNMENT** PROPOSED RIVER ALIGNMENT CONTROL POINT STAGING AREA **WORK AREA EXCLUSION** 

SILT FENCE

CONSTRUCTION ACCESS

LIMITS OF DISTURBANCE

- 1. ALL SPECIFIC EROSION CONTROL BEST MANAGEMENT PRACTICES, INCLUDING WORK AREA ISOLATION, SEDIMENT CONTAINMENT, AND POLLUTION PREVENTION MEASURES SHALL COMPLY WITH ALL PROJECT PERMITS, PROJECT SPECIFICATIONS, THE MAINE DOT BEST MANAGEMENT PRACTICES FOR EROSION CONTROL AND SEDIMENTATION CONTROL MANUAL (MEDOT 2008), AND THE MAINE DEP EROSION AND SEDIMENT CONTROL PRACTICES FIELD GUIDE FOR CONTRACTORS (MEDEP 2014). SEE ADDITIONAL EROSION CONTROL DETAILS ON
- 2. THE CONTRACTOR SHALL SUBMIT A PROJECT SPECIFIC SOIL EROSION AND WATER POLLUTION CONTROL PLAN FOR REVIEW AND APPROVAL BY THE ENGINEER PRIOR TO MOBILIZATION TO THE PROJECT SITE.
- 3. ALL AREAS OF EXPOSED SOIL SHALL BE SEEDED WITH NATIVE VEGETATIVE SPECIES UPON COMPLETION OF FINISHED GRADING IN EACH AREA OF THE PROJECT SITE.
- 2. INSTALL INITIAL EROSION CONTROL MEASURES IN COMPLIANCE WITH PERMITS AND PROJECT SPECIFICATIONS PRIOR TO GROUND DISTURBANCE.
- 3. INSTALL WATER CONTROLS TO ISOLATE RIVER LEFT CHANNEL FOR WORK UPSTREAM OF AND IN THE AREA OF THE DAM.
- 4. ESTABLISH ACCESS AND INITIAL WORK AREA ISOLATION FOR THE REMOVAL OF THE RELIC TRESTLE BRIDGE AND RIVER LEFT PORTION OF THE DAM. TEMPORARY ACCESS SHOULD MAINTAIN DOWNSTREAM RIVER FLOW AND MINIMIZE IMPEDIMENT OF FLOW.
- 5. DEMOLISH RELIC TRESTLE BRIDGE.
- 6. DEMOLISH RIVER LEFT PORTION OF DAM AND ABUTMENT
- 7. BEGIN CONSTRUCTION OF NATURE LIKE FISHWAY CHANNEL.
- 8. BEGIN DECOMMISSIONING TEMPORARY ACCESS FOR UPSTREAM WORK
- 9. ESTABLISH ACCESS AND WORK AREA ISOLATION FOR DOWNSTREAM CHANNEL CONSTRUCTION
- 10. COMPLETE CONSTRUCTION OF NATURE LIKE FISHWAY

- 11. RECONFIGURE EROSION CONTROL MEASURES, AND WORK AREA ISOLATION FOR SOIL MANAGEMENT, AND INSTALLATION OF BANK STABILIZATION.
- 12. COMPLETE SOIL MANAGEMENT AND INSTALLATION OF BANK STABILIZATION
- 13. COMPLETE DECOMMISSIONING OF WORK AREAS ISOLATION, SITE, AND RETURN STAGING.

L							
F					ВВ	MYS	
ŀ					DRAWN	DESIGNED	CHECKED
ł					MB	9/30/2023	
Ī	NO.	BY	DATE	REVISION DESCRIPTION	APPROVED	DATE	PROJECT


MAINE DEPT. MARINE RESOURCES FARWELL DAM FISH PASSAGE LISBON, ME





165 Main Street, Suite 2B Damariscotta, ME 04543 207.315.7014 www.interfluve.com


ACCESS, STAGING, EROSION **CONTROL & SEQUENCING** 


4 of 16























12 POOL


MAINE DEPT. MARINE RESOURCES FARWELL DAM FISH PASSAGE LISBON, ME

TYPICAL SECTION



165 Main Street, Suite 2B Damariscotta, ME 04543 207.315.7014 www.interfluve.com

TYPICAL SECTION



## BULK BAG COFFERDAM NOTES:

BULK BAG COFFERDAM SHALL BE CONSTRUCTED OF SEVERAL UNITS OF BULK BAGS FILLED WITH NATIVE ALLUVIUM OR CLEAN GRAVEL, AND ABUTTED SIDE BY SIDE TO CREATE A ROW THAT ISOLATES THE CONSTRUCTION SITE. IF NECESSARY, GAPS BETWEEN BULK BAGS MAY BE FILLED WITH STREAM GRAVEL TO IMPROVE COFFERDAM SEAL. BULK BAGS SHALL BE CUBE-SHAPED POLYPROPYLENE WOVEN FABRIC BAGS WITH FULLY OPEN TOP, FLAT BOTTOM, FOUR LOOPS, MINIMUM 2-TON WEIGHT CAPACITY, MINIMUM 5:1 SAFETY FACTOR.

IF WATER DEPTH EXCEEDS 85% OF THE BULK BAG HEIGHT, AN ADDITIONAL TOP ROW OF BULK BAGS SHALL BE INSTALLED, SUPPORTED BY TWO BOTTOM ROWS OF BULK BAGS.

BULK BAG COFFERDAM SHALL BE SEALED BY COVERING THE COFFERDAM WITH PLASTIC SHEETING HELD IN PLACE BY STANDARD SANDBAGS FILLED WITH PEA GRAVEL. THE PLASTIC SHEETING SHALL BE DRAPED ALONG THE CHANNEL BOTTOM WITH OUTWARD EDGE OF SHEETING MINIMUM 4-FEET FROM TOE OF COFFERDAM. PLASTIC SHEETING SHALL BE MINIMUM 6-MIL THICKNESS. ROLL LENGTH SHALL BE LONG ENOUGH TO ENSURE THAT ENTIRE LENGTH OF COFFERDAM WILL BE COVERED WITHOUT A SEAM. MINIMUM 12-FT WIDE ROLL SHALL BE USED FOR SINGLE LAYER BULK BAG COFFERDAM. MINIMUM 16-FT WIDE ROLL SHALL BE USED FOR 2-LAYER STACKED BULK BAG COFFERDAM.

THE TERMINAL ENDS OF THE COFFERDAM, WHERE IT CONNECTS TO CHANNEL BANK OR HIGH GROUND, SHALL BE SEALED WITH PLASTIC SHEETING AND STANDARD SANDBAGS.

FARWELL DAM FISH PASSAGE

LISBON, ME

REGULARLY OBSERVE COFFERDAM AND WATERWAY FOR TURBIDITY LEAKS. IF LEAKS ARE DETECTED, CEASE CONSTRUCTION ACTIVITY TO REPAIR OR MODIFY COFFERDAM.


COFFERDAM SHALL BE COMPLETELY REMOVED AFTER CONSTRUCTION IS COMPLETED AND WHEN THERE IS NO VISUALLY DETECTABLE DIFFERENCE IN TURBIDITY BETWEEN THE ISOLATED CONSTRUCTION WATER AND BACKGROUND LEVEL IN THE RECEIVING WATER. BULK BAG FILL AND SANDBAG FILL (WASHED PEA GRAVEL) MAY BE DISPOSED OF ON SITE.

BB MYS DESIGNED DRAWN CHECKED 9/30/2023 MB APPROVED DATE PROJECT NO. DATE REVISION DESCRIPTION



165 Main Street, Suite 2B Damariscotta, ME 04543 207.315.7014 www.interfluve.com

13 of 16



# CONSTRUCTION FORM SEE DETAILS 7-8, SHEET 11 PLACE SECOND CONSTRUCTION FORM SO AS TO ACCOMMODATE 2H:1V PREPARE LEVEL SUB-GRADE FIG E. FIG A. BANK SIDE STREAM SIDE INSTALL SOIL LIFTS ABOVE ROCK TOE **EXISTING GROUND** STAKE THROUGH BOTH 1 FT N ON-WOVEN FABRIC APPLY SEED TO EXPOSED VERTICAL LAYERS 6" BACK FROM AND HORIZONTAL AREAS OF LIFT FRONT EDGE NON-WOVEN COIR (INNER FABRIC) FILL WITH FIG B. **PROPER MATERIAL** FIG F. WOVEN COIR (OUTER FABRIC) **EMBEDMENT** STAKE FABRICS IN PLACE ON 3 FT CENTERS. SEE FABRIC STAKING APPLY AND TRENCHING SHEET 11 SEED TO FIRST 3 FT OF FILL FOLD BOTH INNER AND **OUTER FABRIC OVER FILL APPLY SEED TO** FABRIC FACE FIG C. FIG G. FILL WITH PROPER **MATERIAL** FOLD BOTH INNER AND **OUTER FABRIC OVER FILL** STAKE OUTER FABRIC IN TERMINATION TRENCH. SEE FABRIC STAKING AND TRENCHING SHEET 11 FIG D. PLACE STAPLES ON 18 IN CENTERS. SEE FABRIC STAKING AND TRENCHING SHEET 11 REMOVE CONSTRUCTION PLACE FIRST STAKE FORM PRIOR TO FLATTENING IMMEDIATELY IN FRONT LIFT TO 45 DEG OF NEXT LIFT, OR 2 FT FIG H. (IF 2:1) FROM LIFT TOE IF THIS IS TOP LIFT

MYS

DESIGNED

9/30/2023

DATE

CHECKED

PROJECT

BB

DRAWN

MB

APPROVED

DATE REVISION DESCRIPTION

#### SUGGESTED SEQUENCE FOR PLACEMENT OF FORMS

#### PROFILE VIEW LOOKING INTO BANK




FIG 1. PLACE A ROW OF CONSTRUCTION FORMS ALONG DESIRED CHANNEL ALIGNMENT FOR FIRST FES LIFT.




FIG 2. CONSTRUCT FES LIFTS ALONG LENGTH OF FIRST SET OF FORMS AND THEN BEGIN PLACEMENT OF FORMS AND CONSTRUCTION OF SECOND LIFT.




FIG 3. STAGGER FABRIC OVERLAPS A MINIMUM OF 15 FT BETWEEN LIFTS.

### GENERAL INSTRUCTIONS FOR FABRIC ENCAPSULATED LIFTS

- 1. BANKS MAY BE CONSTRUCTED IN EITHER AN UPSTREAM OR DOWNSTREAM DIRECTION, AS LONG AS THE FABRIC IS OVERLAPPED IN THE PROPER DIRECTION.
- 2. PLACE A SERIES OF THREE OR MORE FORMS ON THE GROUND SO THAT THE FORMS FOLLOW THE PROPOSED STREAM BANK ALIGNMENT. BUTT THE ENDS OF THE FORMS TIGHTLY TOGETHER.
- 3. UNROLL THE OUTER FABRIC PARALLEL TO THE LONG AXIS OF THE CHANNEL AND POSITION IT SO THAT 3 FT EXTENDS FOR EMBEDMENT ON THE BANK SIDE OF THE FORMS (FIG B), AND A MINIMUM 3 FEET EXTENDS LENGTHWISE BEYOND THE LAST FORM FOR OVERLAP. DRAPE THE REMAINDER OF THE FABRIC OVER THE TOP OF THE FORMS ON THE STREAM SIDE (FIG B).
- 4. UNROLL THE INNER FABRIC OVER THE TOP OF THE WOVEN COIR FABRIC (FIG B) AND POSITION IT SO THAT AT LEAST 1 FT OF THE INNER FABRIC EXTENDS AS AN EMBEDMENT LENGTH ON THE BANK SIDE OF THE FORMS (FIG C). DRAPE THE REMAINDER OF THE FABRIC OVER THE TOP OF THE FORMS ON THE STREAM SIDE AND ALIGN THE LONG EDGES OF THE FABRICS. STRETCH AND PULL THE FABRIC LAYERS TO REMOVE WRINKLES.
- 5. APPLY NATIVE SEED MIX TO INNER FABRIC ALONG VERTICAL EDGE OF LIFT (FIG C). PLACE SPECIFIED FILL OVER THE FABRIC ON THE BANK SIDE OF THE FORMS. LEVEL THE FILL AND COMPACT.
- 6. APPLY NATIVE SEED MIX TO TOP OF FILL FROM THE FRONT OF THE LIFT TO 3 FT BACK FROM FRONT OF THE LIFT (FIG C).
- 7. FOLD THE LOOSE ENDS OF THE TWO COIR FABRIC LAYERS BACK OVER THE COMPACTED FILL MATERIAL AND STRETCH TIGHTLY TO REMOVE WRINKLES (FIG D). SECURE WITH WOODEN STAKES.
- 8. REMOVE THE FORMS FROM THE FRONT OF THE COMPLETED LIFTS (FIG. 2). LEAVE THE LAST FORM IN PLACE AT THE END OF THE NEWLY CONSTRUCTED LIFT (FIG. 2).

