



## Section 17

### Wastewater Disposal



## Section 17. Wastewater Disposal

### 17.1 State Standards

Pursuant to the State's Site Law, applicants must report on how wastewater disposal will be managed on site.

### 17.2 Wastewater Disposal Assessment

During the construction phase, wastewater will be produced from temporary toilets and concrete washwater.

The temporary toilet facilities will be provided and serviced by a local, licensed wastewater transporter. No wastewater from the temporary toilets will be disposed of onsite.

Washwater from concrete deliveries will be disposed of on the turbine pads and in upland disturbed areas on site. Waste concrete may be used for the sub-base for access roads and turbine pads. If necessary, the contractor will designate specific washout areas constructed to handle washout water. Washout areas will be located at least 150 feet away from delineated streams and wetlands. No wastewater from the concrete washing process will be disposed of in a natural resource. If used, washout facilities will be inspected daily.

During operation, neither the wind turbines nor the collector systems will produce wastewater.